



Specification (Status: February 2018)

Vegetated Riprap



1) Overview		
Description	ecological appreciation of loose riprap made of armour stones, including filter if neces- sary, through plants (optionally willow log branch cuttings, living fascines, hedge/brush layer)	
	desired vegetation: sectional area by area integration (<i>according to the natural zoning</i>) of indigenous and site-adapted woody plants (<i>trees and/or shrubs – according to plant species and maintenance objectives</i>) into riprap, serving as stepping stone biotope for further species (plants/animals)	
Bank protection	bank protection is ensured through riprap – dimensioned according to GBB ¹⁾ – and filter if necessary, regardless of plants; planting does not provide any bank protection, additional local increase of the bank protection in the course of the continuous development of installed plants however is possible <i>(esp. of the roots)</i>	
	applicable at bank sections already protected with riprap (subsequent vegetation) or at bank sections that require protection (vegetation during riprap installation) and feature a slope inclination of 1:2 or lower	
Ecological potential in comparison with riprap	 support/development of stepping stone biotopes increase of structural and species diversity in the riparian zone increase of the colonization potential for site-adapted animals (esp. birds), avoiding maintenance-pruning enables growth into aquatic zone with age → creation of fish refuge creation of structures to enhance the network between aquatic and terrestrial habitats 	
Advantages/ Disadvantages	 advantages living materials, which can sometimes be cut in-situ bank stability is ensured at all times (after the excavation of plant trenches these must be refilled directly after plantation and covered with armour stones) disadvantages obtaining living material only during dormant season; tree nursery material should be of native origin, possibly limited availability limited installation period (weather, dormant season) high and dense vegetation may influence discharge (maintenance) 	





2) Components and installation			
Components	shoot-forming wood parts and/or woody plants		
Plant elements	native and habitat-adapted woody plants of softwood and hardwood riparian forest (mixture of male and female willow species; tree nursery material only with certification origin)		
Softwood	cuttings (cf. Appendix 1a)		
riparian forest	Ø: 5 - 8 cm (preferably wood parts of straight growth, adapted shrub willows and/or willow trees		
	L: 35 - 80 cm		
	log branch cuttings		
	Ø: 5 - 15 cm (<i>see cuttings</i>) L: 100 - 250 cm		
	living fascines (cf. Appendix 1b)		
	\varnothing branch material: 2 - 5 cm (at least 70% of living branches, i.e. shoot-forming branches, primarily indigenous and site-adapted shrub willows and/or willow trees (limbs with lateral branches) ¹³⁾)		
	arnothing bundle of fascines: 45 - 55 cm		
	L branch material: up to 500 cm		
	brush layers		
	Ø branch material: 2 - 4 cm (<i>primarily indigenous and habitat-adapted shrub willows and/or willow trees (highly branched limbs)</i> ¹³⁾)		
	L branch material: 70 - 100 cm		
	Willow trees: white willow (<i>Salix alba</i>), crack willow Shrub willows: purple willow (<i>Salix purpurea</i>), almont	, ,	
	osier (Salix viminalis)		
Hardwood	hedge layers		
riparian	spillover-resistant saplings which form roots (bare-rooted, twice transplanted seedling)		
forest	L: 60 - 100 cm		
	 Hardwood riparian forest species⁸ (<i>3 plants/m</i>) deper with high flood tolerance¹²: bird cherry (<i>Prunt</i>) 	nding on the flood tolerance: us padus), guelder-rose (Viburnum	
	<i>opulus</i>), Europea common hawthor	in spindle (<i>Euonymus europaea</i>), rn (<i>Crataegus monogyna</i>), rd (<i>Cornus sanguinea</i>),	
	- with low flood tolerance ⁹⁾¹⁰⁾¹²⁾ : European ash (<i>F</i>	a (Cornae canganica), fraxinus excelsior), common hazel a), field maple (Acer campestre)	





Components	bracing wire	
(continued)	(for the purpose of bundling the branches in living fascines)	
Securing	diameter: 0.3 cm, annealed (one bond per running meter)	
material	stakes	
	(for the purpose of staking fascines and brush layers)	
	shoot-forming (indigenous and habitat-adapted willows, additional root formation and	
	denser vegetation)	
	non shoot-forming log woods	
	$\varnothing_{\text{stake}}$: 6 - 8 cm	
	L _{stake} : approx. 100 - 120 cm (<i>depending on the diameter of the fascine</i>)	
Cutting and	cutting of living field-grown wood parts	
installation period	dormancy period (= period between shedding of leaves and budding; respect nature conservation regulations of BNatSchG [Federal Nature Conservation Act] when cutting branches of wild willows)	
	obtaining living wood parts from tree nurseries no time constraints	
	installation of shoot-forming wood parts (cuttings, log branch cuttings, brush layers) ¹¹⁾¹³⁾	
	(during winter dormancy, on frost-free days with unfrozen ground)	
	Ideally: March/April (<i>immediate root formation after installation</i>); depending on location and weather, installation is also possible until May	
	installation of bare rooted woody plants (hedge layer) ¹¹⁾¹³⁾	
	in spring or autumn, hence in the beginning or at the end of dormancy period	
Boundary	distance to water level	
conditions for	planting above mean water level/normal water level	
installation	pay attention to riparian and habitat-adapted bank zonation of species (<i>e.g. softwood and hardwood riparian forest zone</i>)	
	slope inclination	
	≤1:2	
	lighting	
	sun or partial shade	
Installation	excavation of planting trenches or planting holes (cf. Appendix 2)	
instructions	excavation of trenches in the direction of the slope dip down to in-situ soil; if necessary, pre-drill planting holes down to in-situ soil	
	installation (cf. Appendix 2)	
	log branch cuttings and cuttings:	
	(zone: softwood riparian forest)	
	sharpen lower basal ends, drive in planting holes at a distance of 50 cm (<i>borehole must guarantee comprehensive soil contact of planting elements, otherwise, subsequent slurry with sand topsoil mixture</i>) or install in excavated planting trenches; saw off upper ends of log branch cuttings slightly inclined (<i>water runoff during rainfall</i>)	
	living fascines:	
	(zone: softwood riparian forest)	
	installation in planting trenches (<i>basal ends of branches point in the direction of the slope toe</i>); fix fascine crosswise with stakes (cf. Appendix 1b)	





Specification (Status: February 2018)

Installation instructions

(continued)

(zone: softwood riparian forest)

install willow branches inclined to the direction of the flow so that only ¼ of their length protrudes beyond the slope surface (cf. Appendix 1a); place a soil layer of approx. 10 cm on branches

hedge layers:

brush layers:

(zone: hardwood riparian forest)

Installation of saplings (3 *qty. per m*) inclined to the direction of the flow in planting trenches so that only $\frac{1}{4}$ of their length protrudes beyond the slope surface; place a soil layer of approx. 10 cm on saplings

water supply

log branch cuttings/cuttings, fascines, brush /hedge layers must have soil contact (use of slurry material if necessary)

distance of single planting/planting trenches

- distance of single planting: saplings approx. 30 cm; log branch cuttings, cuttings approx. 50 cm
- distance of planting trenches: approx. 500 cm

securing

log branch cuttings/cuttings: after tight installation, no additional securing necessary

living fascines: fixation of fascines crosswise with stakes (one pair of stakes per m; drive in a stake each in front of and behind any coil of the fascine)

brush layers: no additional securing after replacement of armour stones

hedge layers: see brush layers

procedure (cf. Appendix 2)

cuttings/log branch cuttings:

- 1) pre-drilling of a planting hole with a plant drill at a distance of 50 cm or excavation of planting trenches (store armour stones and excavated material at the side)
- 2) installation of a log branch cutting/cutting (*basal ends at the bottom*) and driving log branch cuttings slightly deeper into the ground
- 3) application of slurry of sand/topsoil mixture to the borehole or planting trench
- 4) saw-off upper end of log branch cuttings above the slope surface (approx. 20-50 cm)
- 5) reinstallation of excavated material and stones, stored at the side temporarily (*plant parts may not be damaged in this process*)

living fascines

- 1) excavation of planting trenches (*store armour stones and excavated material at the side*)
- 2) installation of living fascines (basal ends in direction of slope toe)
- 3) fixation of fascines crosswise with stakes
- 4) covering fascines with excavated material (*approx. 3 cm*) stored at the side temporarily
- 5) reinstallation of armour stones laterally in the trenches (carefully in order to prevent damage of plant parts)







lu stallation	brush layers			
Installation instructions	1) excavation of planting trenches (store armour stones and excavated material at the			
(continued)	side)			
(0011011000)	2) installation of a river gr 0/32)	ravel layer of approx. 10 cm in the trench (grading approx.		
		anches inclined to direction of flow on the bedding so that only ides beyond the slope surface		
	4) place a soil layer of ap			
	5) reinstallation of armour stones at the sides of the trenches (<i>carefully, for the purpose of preventing damage of plant parts</i>)			
	6) pruning of branches to max. 10 cm length above the surface of riprap			
	hedge layers			
	1) see brush layers			
	2) see brush layers			
	 3) installation of saplings (<i>3 qty. per m</i>) inclined to direction of flow so that only ¼ of their length protrudes beyond the slope surface 			
	4) installation of a soil lay	er of approx. 10cm on saplings		
	5) reinstallation of armour stones at the sides of the trenches (<i>carefully, for the purp of preventing damage of plant parts</i>)			
	ensuring filter stability			
	through filter-stable revet	ment structure		
3) Mode of ac	tion and load-carryin	n canacity		
•				
Mode of action		ace erosion induced by currents and waves		
	right after installation	ensured through riprap		
	in the long term	additional protection through continuous development of plants		
	protection against slidi pressure	ng of the slope due to drawdown/excessive pore water		
	right after installation	ensured through sufficient mass per unit area and a filter- stable structure of the riprap		
	in the long term	additional protection through continuous development of plants, esp. through root formation in the area of planting trenches (<i>increase of shear strength of in-situ soil (cohe- sion due to roots), local soil nailing</i>)		
	protection against hydr pore water pressure	odynamic soil displacement due to drawdown/excessive		
	right after installation	ensured through sufficient mass per unit area and a filter- stable structure of the riprap		
	in the long term	additional protection through continuous development of plants, esp. root formation in the area of planting trenches (<i>increase of shear strength of the in-situ soil</i> (cohesion due to roots))		
	general			
	shoots of living plant part	s can favour ecologically valuable accumulation of dead wood <i>stural elements</i>) on the slope, while causing an increase of the ne time		

Technical-biological Bank Protections Applied on Inland Waterways



Vegetated Riprap



Toloropoo to	basis: present experiences gained at navigable waterways ^{3) to 7)} and watercourses	
Tolerance to hydraulic	without navigation ¹⁵⁾	
loading	- drawdown: necessary mass per unit area of riprap (verification according to GBB ¹⁾)	
	- wave height: depending on the stone class installed	
	1.0 ^{*)} m ¹⁵⁾ for stone class LMB _{5/40} (stone density: 2.6 t/m ³) 0.3 m <i>(measured load on the test stretch at the river Rhine,</i> <i>test section 1, until now)</i> ^{3) to 6)}	
	- flow velocity	
	close to the bank: depending on the stone size category installed	
	2.6° m/s ¹⁵⁾ for stone class LMB _{5/40} (stone density: 2.6 t/m ³)	
	1.0 m/s <i>(measured load on the test stretch at the river Rhine, test section 1, until now)</i> ^{3) to 6)}	
	*) values apply for the stability of riprap – stone class $LMB_{5/40}$ and bigger (dimensioned according to GBB^{11}) on slope inclinations of 1:3 and smaller –, no sufficient experien-ces on the load-carrying capacity of the plants installed into the riprap yet	
Flooding	flooding tolerance differs depending on the species of woody plants installed	
tolerance	flooding tolerance of softwood riparian species up to 80 days of flooding period per year (basket willow) ¹⁴⁾ up to 130 days (almond and purple willow), respectively 170 days (white willow) ¹⁰⁾¹²⁾¹⁴⁾ (<i>benchmark!</i>)	
	flooding tolerance of hardwood riparian species up to 20 days of flooding period per year (hazel) ^{10),} up to 40 days (ash), respectively 90 days (spindle, hawthorn, viburnum, dogwoods) ¹⁰⁾¹²⁾ (<i>benchmark!</i>)	
	flooding tolerance is additionally influenced by: flooding height, flow, age and growth height of trees and shrubs, flooding period (<i>during growing season or dormancy period</i>), plant vitality	
4) Miscellane	ous	
Maintenance	in general, no need for maintenance.	
	exceptions are:	
	- flood discharge is not sufficiently provided due to vegetation	
	 traffic safety is affected negatively by vegetation (clearance for the purpose of visibility) 	
	- riprap is damaged	
	the following applies thereafter:	
	maintenance measures should be performed non-uniformly and in longer periods according to growth rates (willow trees and shrubby willows) and maintenance objectives	
	maintenance between 1st October and end of February only (according to BNatSchG)	
Examples at German Waterways	- test stretch at the river Weser ²⁾ near Stolzenau, km 241.550 - 242.300, right bank, (test section 12: riprap with willow cuttings/log branch cuttings; VF 14, 14a: riprap and row of alders), installation finished 1989 (<i>considering boundary conditions, very good</i> <i>development is observable until now</i>)	
	- test stretch at the river Rhine ^{3) to 6)} near Lampertheim, km 440.600 - 441.600, right bank, (test section 1: log branch cuttings, willow fascines, brush/hedge layers), installation finished at the end of 2011 (<i>considering boundary conditions, very good development is observable until now</i>)	
	- test stretch at the river Saar between Saarburg and Serrig, km 15.000, right bank, installation finished in 2008 (<i>considering boundary conditions, very good development is observable until now</i>)	

Technical-biological Bank Protections Applied on Inland Waterways



Vegetated Riprap



BAW (2011): Bundesanstalt für Wasserbau (Hrsg.), Grundlagen zur Bemessung von Böschungs- und Sohlensicherungen an Binnenwasserstraßen (GBB 2010), Eigenverlag, Karlsruhe 2011.
BAW, BfG (2008): Bundesanstalt für Wasserbau, Bundesanstalt für Gewässerkunde, Untersuchungen zu alternativen technisch-biologischen Ufersicherungen an Binnenwasserstraßen - Teil 2: Versuchsstrecke Stolzenau/Weser, Eigenverlag, Karlsruhe, Koblenz 2008.
BAW, BfG (2012): Einrichtung einer Versuchsstrecke mit technisch-biologischen Ufersicherungen, Rhein, km 440,600 bis km 441,600 (rechtes Ufer), Erster Zwischenbericht – Randbedingungen, Einbaudokumentation, Monitoring, 25.01.2012, available at http://ufersicherung.baw.de/de/index.html
BAW, BfG (2015): Einrichtung einer Versuchsstrecke mit technisch-biologischen Ufersicherungen, Rhein, km 440,600 bis 441,600 (rechtes Ufer), Teilbericht Stand- sicherheit und Unterhaltung, Monitoringergebnisse 11/2012 bis 10/2013,
30.03.2015, abrufbar unter http://ufersicherung.baw.de/de/index.html
BAW, BfG (2013): Einrichtung einer Versuchsstrecke mit technisch-biologischen Ufersicherungen, Rhein, km 440,600 bis km 441,600 (rechtes Ufer), Zweiter Zwischenbericht – Erste Monitoringergebnisse 2012, 20.06.2013, available at http://ufersicherung.baw.de/de/index.html
BAW, BfG, WSA MA (2016): Einrichtung einer Versuchsstrecke mit technisch- biologischen Ufersicherungen, Rhein, km 440,600 bis km 441,600 (rechtes Ufer), Fünfter Zwischenbericht – Monitoringergebnisse 11/2014 bis 10/2015, 08/2016, abrufbar unter http://ufersicherung.baw.de/de/index.html
BAW, BfG: Internetportal zur Thematik "Alternative technisch-biologische Ufersiche- rungen an Binnenwasserstraßen", http://ufersicherung.baw.de/de/index.html
Bundesanstalt für Gewässerkunde (1965): Der biologische Wasserbau an den Bundeswasserstraßen. Verlag Eugen Ulmer. Stuttgart
Dister, E. (1983): Zur Hochwassertoleranz von Auwaldbäumen an lehmigen Stand- orten. – Verh. d. Ges. f. Ökologie, Bd. X: 325-335.
Dister, E. (1988): Ökologie der mitteleuropäischen Auenwälder. Wilhelm-Münker- Stiftung. Heft 19. S. 6-30. Siegen
Schiechtl, H. M. & R. Stern (2002): Naturnaher Wasserbau. Anleitung für ingenieur- biologische Bauweisen. Berlin.
Späth, V. (1988): Zur Hochwassertoleranz von Auenwaldbäumen, Natur und Land- schaft 63, 1988, S. 312 bis 315
Stowasser, A. (2011): Potenziale und Optimierungsmöglichkeiten bei der Auswahl und Anwendung ingenieurbiologischer Bauweisen im Wasserbau. Schriftenreihe Institut für Umweltplanung Leibniz Universität Hannover. Cuvillier Verlag Göttin- gen.
Westhus, W. (1986): Beobachtungen zur Überflutungstoleranz von Gehölzen und daraus abgeleitete Pflanzvorschläge. Hercynia N. F., Leipzig 23 (1986) 3, S. 346-353.
DWA (2016): Technisch-biologische Ufersicherungen an großen und schiffbaren Binnengewässern, Merkblatt DWA-M519, März 2016






5) Institutions / link	
Addresses,	Federal Waterways Engineering and Research Institute
persons of contact	Earthworks and Bank Protection Section (G4) Petra Fleischer (direction): +49 (0)721 9726-3570 @: petra.fleischer@baw.de
	Federal Institute of Hydrology
	Vegetation Studies and Landscape Management Section (U3) Dr. Andreas Sundermeier: +49 (0)261 1306-5151 @: ag-ufersicherung@bafg.de
Link	For further information, please see: http://ufersicherung.baw.de/de
















Specification (Status: February 2018)



Appendix 2

Sample Photos

Source: Test Stretch Lampertheim/Rhine³⁾⁴⁾⁵⁾⁶⁾

photos: BAW/BfG



(1) excavation of a planting trench in the loose armour stone revetment down to in-situ soil; Nov. 2011



(2) willow log branch cuttings installed into the planting trenches; Nov. 2011



(3) Willow fascines placed into the planting trenches and fixed with stakes; end of Nov. 2011



(4) bare-rooted saplings for the purpose of obtaining hedge layers; end of Nov. 2011



(5) installation of hedge layers in excavated planting trenches; end of Nov. 2011




(6) planting trench with one-year-old brush and hedge layers; Jan. 2013





Vegetated Riprap Specification (Status: February 2018)





(7) continuous development of willow log branch cuttings; April 2012



(9) continuous development of vegetated riprap; June 2012



(8) shoots of willow fascines; end of April 2012



(10) willow cuttings with shoots; June 2012



(11) willow log branch cutting with developed aerial roots (adventitious roots); Aug. 2013



(12) willow log branch cuttings 2 $^{1\!\!/}_2$ years after installation; May 2014