



PIANC

WG Report n° 173 - 2017



MOVABLE BRIDGES AND ROLLING GATES DESIGN, MAINTENANCE AND OPERATION LESSONS LEARNT

The World Association for Waterborne Transport Infrastructure



PIANC

The World Association for
Waterborne Transport Infrastructure

PIANC REPORT N° 173

INLAND NAVIGATION COMMISSION

MOVABLE BRIDGES AND ROLLING GATES DESIGN, MAINTENANCE AND OPERATION LESSONS LEARNT

2017

PIANC has Technical Commissions concerned with inland waterways and ports (InCom), coastal and ocean waterways (including ports and harbours) (MarCom), environmental aspects (EnviCom) and sport and pleasure navigation (RecCom).

This report has been produced by an international Working Group convened by the Inland Navigation Commission (InCom). Members of the Working Group represent several countries and are acknowledged experts in their profession.

The objective of this report is to provide information and recommendations on good practice. Conformity is not obligatory and engineering judgement should be used in its application, especially in special circumstances. This report should be seen as an expert guidance and state-of-the-art on this particular subject. PIANC disclaims all responsibility in the event that this report should be presented as an official standard.

PIANC Secrétariat Général
Boulevard du Roi Albert II 20, B 3
B-1000 Bruxelles
Belgique

<http://www.pianc.org>

VAT BE 408-287-945

ISBN 978-2-87223-243-7

© All rights reserved

TABLE OF CONTENTS

1	Introduction	12
1.1	Aims of WG 173 and Scope of the Report.....	12
1.2	Terms of Reference.....	13
1.3	Members of PIANC WG 173.....	14
1.3.1	Working Group Members	14
1.3.2	National Support Team Members	16
1.3.3	Corresponding Members	16
1.4	Acknowledgments and Site Visits	18
2	Conclusions and Summary of Report	19
2.1	Rolling Gates	19
2.1.1	Rolling Gate Considerations.....	21
2.2	Panama Canal Rolling Gate.....	24
2.3	Movable Bridges.....	27
2.3.1	Movable Bridge Considerations	28
2.4	Multi-Criteria Analysis	29
2.5	Appendices.....	30
2.5.1	Appendix A: Risk-Based Guidelines.....	30
2.5.2	Appendix B: Automation, Software, Standardisation and Remote Control	30
2.5.3	Appendix C: Electrical Drive Systems	30
2.5.4	Appendix D: Rolling Gate Installation Table	30
2.5.5	Appendix E Safety and Reliability Functions for Movable Bridges and Locks	30
2.5.6	Appendix F Port of Antwerp Best Maintenance Practices Rolling Gates.....	30
3	Movable Bridges and Rolling Gates – General Discussion.....	31
3.1	Rolling Gates and Movable Bridges Defined	31
3.1.1	Rolling Gates.....	31
3.1.2	Movable Bridges	31
3.2	History of Rolling Gates	31
3.2.1	United States.....	31
3.2.2	Antwerp (Belgium) History of Rolling Gates	34
3.2.3	Dutch History of Rolling Gates	35
3.2.4	German History of Rolling Gates.....	37
3.3	History of Movable Bridges	38
3.3.1	General Discussion	38
3.3.2	United States Historical Movable Bridges	40
3.3.3	Dutch History of Movable Bridges	42
3.4	Common Features of Rolling Gates and Movable Bridges	44
3.4.1	Common Components	44
3.4.2	Common Purpose	45
3.4.3	Remote Operation	45
3.5	Design Differences between Rolling Gates and Movable Bridges.....	46
3.5.1	Standard of Reliability	46
3.5.2	Other Design Differences	46
3.6	Safety	47
3.6.1	European Union Machinery Directive	47
3.6.2	EU Machinery Directive and Risk Assessment	48
3.6.3	Safety of Operators and Maintenance Personnel.....	50
3.6.4	Machine Guarding	50
3.7	Sustainability.....	51
3.7.1	Sustainable Procurement.....	51
3.7.1.1	Sustainability as a Quality Aspect.....	51
3.7.1.2	Carbon Dioxide Performance Ladder	51
3.7.1.3	Software Tool	51
3.7.2	Sustainable Solutions.....	52
3.7.2.1	Lighting Solutions	52
3.7.2.2	LED Pilot Project on Krammersluizen (lock)	53
3.7.2.3	Industrial Harbour Lock Germany.....	54
3.7.3	Lubricants.....	54
3.7.3.1	Types of EA Lubricants	54
3.7.3.2	Definition	54
3.7.3.3	Labelling Organisations	55
3.7.3.4	Other Standards	56
3.7.4	Self-Lubricated Materials.....	56
4	Rolling Gates General Design.....	59

4.1	Definition and Types of Rolling Gates and General Design	59
4.2	Design Considerations	61
4.2.1	Wheelbarrow Design	61
4.2.2	Classical Support System	65
4.2.3	Buoyancy	67
4.2.4	Operating Speed	69
4.2.5	Redundancy	70
4.2.5.1	Drive Mechanism	71
4.2.5.2	Filling and Emptying System	71
4.2.5.3	Ship Impact Provisions	71
4.2.6	Ship Impact	71
4.2.7	Corrosion Protection	73
4.2.8	Gate Seals	74
4.3	Components	75
4.3.1	Gate Body	75
4.3.2	Skinplate	76
4.3.3	Framing	78
4.3.4	Undercarriage	80
4.3.5	Upper Carriage of a Wheelbarrow Gate	82
4.3.6	Guiding Elements of the Gate during Opening and Closing	84
4.3.7	Filling and Emptying System for Lock	84
4.3.8	Roller Track and Wheels	85
5	Rolling Gate Drive Systems	87
5.1	Drive System	87
5.1.1	Wire Rope Tension Systems	91
5.1.2	Hydraulic Drives	93
5.1.3	Chain Systems and Rack and Pinion Systems	96
5.1.4	Control Systems	99
5.1.5	Safety Functions	99
5.2	Maintenance	99
5.2.1	Control of Debris and Silt	100
5.2.2	Other Considerations	101
5.2.3	Maintenance Frequency	102
5.2.4	Cold Weather Operation	102
6	Sliding Gates	107
6.1	Concept and General Discussion	107
6.2	Sliding Gate Design PWA Lock	107
7	Panama Canal Rolling Gates	112
7.1	Introduction	112
7.2	Panama Canal Expansion Project	113
7.3	Description of Gates	115
7.4	Drive System	119
7.4.1	Wire Rope Tension System	121
7.4.2	Wire Rope Design	123
7.5	Design Features	123
7.5.1	Buoyancy	125
7.5.2	Carriage Design	126
7.6	Earthquake Design	129
7.7	Lessons Learnt and Best Practice	130
8	Antwerp Locks Rolling Gates	132
8.1	Introduction	132
8.1.1	Kieldrecht Lock	133
8.1.2	Berendrecht Lock and Zandvliet Lock	136
8.2	Rolling Gate Design	137
8.3	Drive Machinery	138
8.4	Best Practice	141
9	German Locks Rolling Gates	143
9.1	Introduction	143
9.2	Kaiser Lock Bremerhaven	143
9.3	North Lock Bremerhaven	148
9.4	Fishery Port Lock – Bremerhaven	150
9.5	5th Lock Brunsbüttel	152
10	Dutch Rolling Gates	155
10.1	Introduction	155
10.2	Terneuzen Locks	155
10.2.1	The Western Lock	156

	10.3	Meppelerdiep Lock.....	159
	10.4	Northern Lock at IJmuiden	163
11		Movable Bridges General Design	166
	11.1	General.....	166
	11.2	Bascule Bridges	167
	11.2.1	Trunnion Type	167
	11.2.2	Rolling Bascule Type.....	168
	11.2.3	Remote-Counterweighted Bascule Type.....	169
	11.2.4	Non-Counterweighted Bascule Bridges.....	171
	11.3	Swing Bridges	171
	11.4	Vertical Lift Bridges	172
	11.5	Uncommon Types of Movable Bridges	174
	11.6	Design Standards.....	175
	11.6.1	American AREMA Specifications for Movable Railroad Bridges	175
	11.6.2	United States AASHTO Specifications for Movable Highway Bridges.....	175
	11.6.3	NEN 6786, Rules for the Design of Movable Bridges Netherlands (in Dutch)	176
	11.6.4	NEN 6787, Machine Safety of Movable Bridges (in Dutch)	176
	11.6.5	German ZTV-Ing Part 9 - Additional Technical Specifications for Movable Bridges).....	177
	11.6.6	German Standard DIN 19704.....	177
	11.6.7	European FEM Standard.....	177
	11.6.8	Belgian Design Standard.....	178
	11.6.9	USA, Florida DOT Structures Manual	178
	11.6.10	CSA S-6 Canadian Highway Bridge Design Code	178
	11.7	Bridge Design	178
	11.7.1	Design Loads and Design Considerations	179
	11.7.1.1	Wind Loading.....	179
	11.7.1.2	Operating Speed	179
	11.7.2	Movable Bridge Systems and Components	180
	11.7.3	Support System for Movable Bridges	181
	11.7.3.1	Structural Elements of the Movable Bridge Support System	181
	11.7.3.2	Mechanical Element of the Movable Bridge Support System	181
	11.7.4	Balance System for Movable Bridges.....	181
	11.7.4.1	Structural Elements of the Movable Bridge Balance System.....	181
	11.7.4.2	Mechanical Elements of the Movable Bridge Balance System	181
	11.7.4.3	Counterweights and Balancing.....	181
	11.8	Movable Bridge Sustainability and Environmental Issues	182
	11.8.1	Noise Considerations	182
	11.8.2	Zero Energy Bridge	183
12		Movable Bridge Drive Systems.....	185
	12.1	Drive Systems for Movable Bridges	185
	12.1.1	Vertical Lift Bridges	185
	12.1.2	Trunnion Bascule Bridges	190
	12.1.3	Rolling Bascule Bridges	192
	12.1.4	Swing Bridges	194
	12.2	Mechanical Elements of the Movable Bridge Drive System	196
	12.2.1	Shock Absorbers and Spring Elements.....	196
	12.2.2	Brakes	196
	12.2.3	Wire Rope	198
	12.3	Electrical Power Components of the Movable Bridge Drive System	198
	12.4	Control Systems for Movable Bridges	198
	12.4.1	Mechanical Elements of the Movable Bridge Control Systems	198
	12.4.2	Electrical Elements of the Movable Bridge Control Systems.....	198
	12.4.3	Interlocking System for Movable Bridges	199
	12.4.4	Holding Bridge in Fixed Position	199
	12.5	Navigation Guidance Systems for Movable Bridges.....	200
	12.6	Traffic Control Systems for Movable Bridges	201
	12.7	Movable Bridge Control House.....	201
	12.8	Maintenance Considerations for Movable Bridges	201
13		Safety of Movable Bridges	203
	13.1	General Discussion.....	203
	13.2	Safety Systems and Interlock Requirements.....	203
	13.2.1	Audible Systems	203
	13.2.2	Closed Circuit Television - CCTV	203
	13.2.3	Flashing Lights, Traffic Lights and Road Gates.....	204
	13.2.4	Radar Systems.....	204
	13.2.5	VHF Transceivers.....	204

	13.2.6	Vessel Detectors and Ship Collision.....	204
	13.2.7	Electrical Interlocks	206
	13.2.8	Vehicle Sensor	206
	13.3	Remote Operation	207
	13.4	Safety Standards	207
	13.4.1	Safety Codes.....	207
	13.5	Pedestrian Safety	208
	13.6	Vehicle Safety	209
	13.6.1	Traffic Control.....	209
	13.6.2	Dutch Traffic Control Study	209
	13.6.3	Barriers.....	211
14		Movable Bridges Netherlands.....	214
	14.1	Ketelbrug	214
	14.1.1	Mechanical Features	215
	14.1.2	Safety	218
	14.1.3	Lessons Learnt.....	218
	14.1.3.1	Traffic Jam Detector	218
	14.1.3.2	Accident 1	218
	14.1.3.3	Accident 2	219
	14.2	Botlekbrug	219
	14.2.1	Balancing of the Bridge	222
	14.2.2	Driveline	222
	14.2.3	Bridge Locking System.....	225
	14.2.4	Guiding.....	226
	14.2.5	Operation	226
	14.2.6	Control.....	226
	14.2.7	Energy Supply	227
	14.2.8	Operation Time	227
	14.2.9	Manufacturing	227
	14.2.10	Maintenance and Replacement.....	228
	14.3	Van Brieneoordbrug	228
	14.3.1	History	229
	14.3.2	Mechanical Features.....	230
	14.3.3	Lessons Learnt.....	234
15		Movable Bridges Germany.....	235
	15.1	Kattwyk Movable Bridge.....	235
	15.2	Rethe Bridge.....	237
	15.3	Swing Bridge North Lock Bremerhaven.....	238
	15.3.1	Bridge History.....	239
	15.3.2	Bridge Drive Systems.....	240
	15.3.3	Rail Track Crossings	240
	15.3.4	Safety Equipment.....	240
	15.3.5	Reconstruction 2005	241
16		Movable Bridges St. Lawrence Seaway	242
	16.1	Welland Canal Bridge #5	242
	16.1.1	Machinery and Wire Ropes	243
	16.1.2	Traffic Control.....	246
	16.1.3	Bridge History.....	246
	16.1.4	Control System.....	247
	16.1.5	Preventative Maintenance Programme	247
	16.1.6	Maintenance Stairs.....	248
	16.1.7	Lessons Learnt and Best Practices	249
	16.2	Welland Canal Bridge #6	250
	16.2.1	Drive Machinery	251
	16.2.2	Electrical Power	253
	16.2.3	Bridge #6 History.....	254
	16.2.4	Bridge #6 Control System	254
	16.2.5	Lessons Learnt and Best Practices	255
17		Movable Bridges United Kingdom.....	256
	17.1	London Bridge – Tower Bridge.....	256
	17.1.1	Original Operating Equipment	257
	17.1.2	Developments and Upgrades	259
	17.1.3	Current Operational Equipment.....	259
	17.2	Poole Bridge	261
	17.2.1	Electrical Control Equipment and Instrumentation	261
	17.2.2	Electro-Mechanical and Gearing Operating Equipment	262

17.2.3	Planned Upgrades.....	263
17.3	Twin Sails Bridge	263
17.3.1	Mechanical and Hydraulic Operating Equipment	265
17.3.2	Electrical Control Equipment and Instrumentation	266
18	Movable Bridges United States.....	267
18.1	Introduction	267
18.2	Duluth Aerial Lift Bridge	267
18.2.1	General Discussion	267
18.2.2	Brief History of the Bridge	268
18.2.3	Ownership and General Operation of the Bridge	271
18.2.4	Cold Weather Considerations	272
18.2.5	Security and Safety	273
18.2.6	Operation and Maintenance	274
18.2.7	Controls.....	274
18.3	Rock Island Arsenal Swing Bridge	275
18.3.1	General Information.....	275
18.3.2	Drive Systems and Power	278
18.3.3	Rehabilitation Work and Lessons Learned.....	281
18.3.4	Centering Problem and Lift Cylinders.....	282
18.4	Florida (United States) Movable Bridges	283
18.4.1	General Information.....	283
18.4.2	Design Guidelines	284
18.4.3	Hydraulic Drive System Requirements.....	285
18.5	Bonneville Swing Bridge Columbia River USA	286
18.5.1	General Information.....	286
18.5.2	Bridge Design.....	287
18.5.3	Center Bearing	288
18.5.4	Balance Wheels	289
18.5.5	Hydraulic Drive Cylinders.....	290
18.5.6	Center Wedges	292
18.5.7	End Lifts, Wedges, Bearings	292
18.5.8	Conclusions and Lesson Learnt	293
19	References.....	294
19.1	Websites	296
Appendix A: Risk-Based Guidelines.....		297
Appendix B: Automation, Software, Standardisation and Remote Control		318
Appendix C: Electrical Drive Systems.....		345
Appendix D: Rolling Gate Installation Table		372
Appendix E: Safety and Reliability Functions for Locks and Movable Bridges		373
Appendix F: Best Maintenance Practices Port of Antwerp Rolling Gates.....		376

LIST OF FIGURES

Figure 1.1:	Working Group members in front of the new Panama Canal rolling gates	14
Figure 1.2:	Working Group members in the Bremerhaven Kaiser lock.....	17
Figure 2.1:	Opening of the new Kieldrecht lock	19
Figure 2.2:	Opening of the new Panama Canal third lane	20
Figure 2.3:	Opening day of the new Panama Lock Agua Clara, Panama.....	20
Figure 2.4:	New Lock at IJmuiden – location shown in red highlight	21
Figure 2.5:	Juliana lock in Gouda, the Netherlands.....	22
Figure 2.6:	Compression column for Panama lock gate – lower carriage.....	26
Figure 2.7:	New Botlek vertical lift bridge Netherlands constructed 2016.....	27
Figure 3.1:	Davis Island lock and dam, downstream rolling gate, near Pittsburgh, Pennsylvania, USA, 1885	32
Figure 3.2:	Lock 37 rolling gate drawing.....	33
Figure 3.3:	Lock 37 rolling gate (postcards of Cincinnati from 1905).....	33
Figure 3.4:	Lock 37 Steamer Ramona and rolling gate (postcards of Cincinnati from 1905).....	34
Figure 3.5:	King Leopold II visits the Royers lock in 1907	34
Figure 3.6:	Bonaparte lock with a view on Bonaparte dock and Willem dock	35
Figure 3.7:	BelgenLand II, Red Star Line.....	35
Figure 3.8:	Cellesuis Kampen 1868.....	36
Figure 3.9:	IJmuiden lock showing existing rolling gates	36
Figure 3.10:	Kaiser lock from 1904 with rolling gates in foreground	37

Figure 3.11: Brunsbüttel lock gate construction 1914 © WSA Brunsbüttel	38
Figure 3.12: Column of Marcus Aurelius erected in 193 A.D. in Rome showing a pontoon bridge.....	39
Figure 3.13: London bridge constructed 1209.....	39
Figure 3.14: Sketch by Leonardo da Vinci dating from 1482 for the design of an unequal-armed swing bridge	39
Figure 3.15: Buzzard Bay Vertical-Lift Bridge, Cape Cod, Massachusetts during construction in 1935 to replace an existing Strauss Heel Trunnion Bascule Bridge.	40
Figure 3.16: Rock Island Swing Bridge Mississippi River – United States.....	41
Figure 3.17: Construction of the Madison Street Bascule Bridge in 1922 to Replace an Existing Swing Bridge, Chicago, IL.....	42
Figure 3.18: Modern version of what in the Netherlands is called a drawbridge.....	42
Figure 3.19: The first bridge made of steel was probably the ‘Stokkenbrug’ built in 1837 in Rotterdam.....	43
Figure 3.20: ‘Stokkenbrug’ bridge painting by David Welle (Historisch Museum Rotterdam)	43
Figure 3.21: The ‘Spijkerbrug’ in Middelburg is a bridge built in 1853 and is still in use	44
Figure 3.22: Photo of rolling gate machinery and movable bridge machinery	44
Figure 3.23: Photo of rolling gate with roadway (Bremerhaven).....	45
Figure 3.24: Control Building between Zandvliet Lock and the Berendrecht lock.....	46
Figure 3.25: Flow chart for development of EU Machinery Directive.....	48
Figure 3.26: Machinery guards for vertical lift bridge St Lawrence Seaway Canada.....	50
Figure 3.27: RWS A44 roadway lighting project.....	53
Figure 3.28: Krammersluizen lock.....	53
Figure 3.29: Synthetic ester hydraulic fluid with EA labelling.....	55
Figure 4.1: Diagram of a rolling gate	59
Figure 4.2: New Panama Canal rolling gates before being installed in gate recess	60
Figure 4.3: Rolling gate types (Courtesy R.A. Daniel)	61
Figure 4.4: Wheelbarrow system Brunsbüttel upper carriage at recess end and lower carriage at chamber end of gate	62
Figure 4.5: Wheelbarrow system Panama Canal also showing buoyancy tanks and compression column	63
Figure 4.6: Berendrecht lock rolling gate wheelbarrow design	64
Figure 4.7: North lock Bremerhaven rolling gate recess – wheelbarrow design	65
Figure 4.8: Central support system of gate of the Northern lock in IJmuiden:	66
Figure 4.9: Kaiser lock rolling gate and carriage with the classical support system – double supports system.....	67
Figure 4.10: New Kieldrecht lock rolling gate being floated into place.....	69
Figure 4.11: Emperors (Kaiser) lock dewatered showing both rolling gates	70
Figure 4.12: New lock IJmuiden ship impact scenarios.....	72
Figure 4.13: Ship arrestor in extended position and activated for energy dissipation	73
Figure 4.14: Ship arrestor in retracted position.....	73
Figure 4.15: Kieldrecht lock stone sealing face	75
Figure 4.16: Different types of supports for rolling gates	76
Figure 4.17: Rolling gate cross-section and structural arrangement	77
Figure 4.18: Rolling gates of the new Panama Canal showing side panels	79
Figure 4.19: Rolling gate of the new Kieldrecht lock showing the framing system	79
Figure 4.20: Rolling gate framing of Kieldrecht lock rolling gates in Antwerp, Belgium	80
Figure 4.21: Rolling gate undercarriage with two supports.....	81
Figure 4.22: Rolling gate wheelbarrow system 5 th ship lock Brunsbüttel.....	82
Figure 4.23: Detail connection gate upper carriage-double support.....	83
Figure 4.24: Upper carriage with two supports.....	83
Figure 4.25: Central support system of the upper carriage, Panama	83
Figure 4.26: North lock – Bremerhaven – Rolling gate with sluice gate incorporated.....	85
Figure 4.27: Panama crane rail system	86
Figure 4.28: New block rails for Kaiser lock.....	86
Figure 5.1: Wire rope drive Kaiser lock Bremerhaven and Van Cauwelaert lock Antwerp	87
Figure 5.2: Wire rope drive machinery layout	88
Figure 5.3: Machinery Van Cauwelaert lock and alternate lay of wire rope Berendrecht lock	88
Figure 5.4: Machinery of wire rope driven rolling gates: Panama Canal 3 rd set of locks and Berendrecht lock in Antwerp, Belgium;	89
Figure 5.5: Kaiser Lock Bremerhaven – machinery rolling gate recess and wire rope cables – note the guide rollers.....	89
Figure 5.6: Operating mechanism for a rolling gate with two-sided operating mechanism with two cable drums	90
Figure 5.7: Operating mechanism of a rolling gate with a two-sided operating mechanism and single cable drum Hansweert.....	91
Figure 5.8: Pneumatic cable tension system and load cells – Panama Canal.....	91
Figure 5.9: Pneumatic cable tension system – Panama.....	92

Figure 5.10: Kaiser lock Bremerhaven wire rope tensioning system	92
Figure 5.11: Kaiser lock Bremerhaven wire rope cylinders for tensioning	93
Figure 5.12: Cable tension control device (double acting)	93
Figure 5.13: Northern lock at IJmuiden – hydraulic drive system	94
Figure 5.14: Northern lock at IJmuiden – hydraulic motor	95
Figure 5.15: Northern lock at IJmuiden – hydraulic power unit	95
Figure 5.16: Chain drive system layout Brunsbüttel	96
Figure 5.17: Chain drive North lock Bremerhaven (Push/Pull System) and Fischereihafenschleuse (Pull System)	96
Figure 5.18: Chain drive system – Fischereihafenschleuse (Pull System)	97
Figure 5.19: Rack system Juliana lock in Gouda	97
Figure 5.20: Juliana lock in Gouda	98
Figure 5.21: Rack system Juliana lock in Gouda	98
Figure 5.22: Upper carriage of the New Sea Lock in IJmuiden, the Netherlands	99
Figure 5.23: Internal gate structure and mixer for debris and sediment control	100
Figure 5.24: Venturi Inlet	100
Figure 5.24: Venturi system inlet detail	101
Figure 5.26: Cross-section of rolling gate for rail access	101
Figure 5.27: Electrically driven propeller unit in Trollhätte canal	103
Figure 5.28: Air bubble ice barriers in Trollhätte canal	103
Figure 5.29: Air diffuser utilising a rubber check valve	104
Figure 5.30: Air released along lockside in Trollhätte canal	104
Figure 5.31: Soo locks ice conditions	105
Figure 5.32: Floating ice in the Krammer lock approach	106
Figure 6.1: Hydrostatic Bearing – PWA Lock	107
Figure 6.2: Sliding gate – PWA Lock	108
Figure 6.3: Sliding gate PWA Lock removed for maintenance – note hydrofeet on both ends of gate	108
Figure 6.4: Sliding gate PWA Lock showing sluice gates	109
Figure 6.5: Sliding gate PWA Lock	110
Figure 6.6: Sliding gate PWA Hydrofoot bearing	110
Figure 6.7: PWA Hydrofoot bearing supply system and filtration system	111
Figure 6.8: PWA Hydrofoot bearing supply manifold	111
Figure 6.9: PWA Hydrofoot cross section	111
Figure 7.1: New Agua Clara Lock Panama Canal	113
Figure 7.2: View of finished Neo-Panamax Locks with water saving basins to left	114
Figure 7.3: New third lane rolling gate	115
Figure 7.4: Panama gate numbering from Gatun Lake to ocean	116
Figure 7.5: Panama Gates being rolled off submersible transport ship four gates at a time	117
Figure 7.6: Lower rails of the Panama rolling gate	117
Figure 7.7: Schematic detail of gate cross-section	118
Figure 7.8: Gate drive – upper and lower carriage assemblies	118
Figure 7.9: Panama gate being positioned into recess by SPMT	119
Figure 7.10: Panama gates and machinery building	120
Figure 7.11: Panama Canal new drive system	120
Figure 7.12: Panama Canal drive system gearbox and motor	121
Figure 7.13: Turning wheel for wire rope cable	121
Figure 7.14: Panama Canal wire rope winch drum	122
Figure 7.15: Panama Canal wire rope tension system accumulator	122
Figure 7.16: Steel wire rope reeving diagram with ropes for gate opening/closing in red and green; for cable tensioning in blue and orange	123
Figure 7.17: Bulkhead being tested to isolate gate in slot for maintenance	124
Figure 7.18: Gate modules fabricated in shop are assembled in dock area	125
Figure 7.19: Pacific lock – lockhead 1 rolling gate recess looking from top – rails for upper carriage being installed and aligned	125
Figure 7.20: Compression column (a) and lower carriage (b) of the Panama Canal rolling gates (from ACP and R.A Daniel)	127
Figure 7.21: Upper carriage main components	128
Figure 7.22: Lower carriage detail	129
Figure 7.23: Atlantic Lock opening and rolling gates shown in recess	131
Figure 8.1: Port of Antwerp locks showing overall lengths	133
Figure 8.2: Zandvliet & Berendrecht lock parallel to each other	133
Figure 8.3: Kieldrecht lock rolling gate installed in the wet	134
Figure 8.4: Kieldrecht lock rolling gate being installed in recess	135
Figure 8.5: Kieldrecht lock Installation of upper carriage	135
Figure 8.6: Berendrecht lock rolling gate	136
Figure 8.7: Zandvliet lock rolling gate	136

Figure 8.8: Spare carriage assembly at Zandvliet	137
Figure 8.9: Rolling gate of the Van Cauwelaert lock in Antwerp, Belgium	137
Figure 8.10: Wire rope support rollers	138
Figure 8.11: Rolling gate machinery showing torque tube and gearbox at Berendrecht lock	139
Figure 8.12: Drive machinery Kallo lock	139
Figure 8.13: Drive machinery and winch drums Van Cauwelaert lock.....	140
Figure 8.14: Turning wheel in the gate chamber	140
Figure 8.15: Mixers in use for rolling gates	141
Figure 8.16: Rail maintenance caisson.....	141
Figure 8.17: Repairing rails inside the dewatering caisson.....	142
Figure 8.18: Before and after photos of the walkway inside the gate chamber.....	142
Figure 9.1: Kaiser lock and rolling gate looking towards the Weser River	144
Figure 9.2: Kaiser lock upper rolling gate removed and used as a bulkhead for dewatering	144
Figure 9.3: Kaiser lock new carriage assembly and removed carriage assembly.....	145
Figure 9.4: Kaiser lock removed rail tracks and new rail tracks	145
Figure 9.5: Kaiser lock – Overview of the gate with the upper and lower part of the gate	146
Figure 9.6: Kaiser lock Inside of Rolling Gate.....	146
Figure 9.7: Kaiser lock hydraulic machinery for raising upper gate	146
Figure 9.8: Kaiser lock hydraulic cylinder for lifting the gate	147
Figure 9.9: Kaiser lock hydraulic cylinders used for moving roadway.....	147
Figure 9.10: Kaiser lock 90 degree drive gear (planetary gear set) for the rolling gate	148
Figure 9.11: Kaiser lock carriage assembly.....	148
Figure 9.12: North lock rolling gate.....	149
Figure 9.13: Spare rolling gate North lock	149
Figure 9.14: North lock drive chain for rolling gate	149
Figure 9.15: Electric drive machinery for North lock	150
Figure 9.16: Lower end of Fishery lock – note use of rolling gate as a highway bridge across the lock	150
Figure 9.17: Larger chamber – upper end rolling gate.....	151
Figure 9.18: Movable roadway using hydraulic cylinders (lift slab)	151
Figure 9.19: Hydraulic system and reservoir	151
Figure 9.20: Back up hydraulic system (redundancy)	152
Figure 9.21: Hydraulic drive motor Fishery lock.....	152
Figure 9.22: 5 th Lock Brunsbüttel – complete gate with gate recess and drive system.....	153
Figure 9.23: 5 th Lock Brunsbüttel gate with pontoon to improve floating stability.....	153
Figure 9.24: 5 th Lock Brunsbüttel – Gate Body with all included parts (water hydraulics, oil hydraulic system, drive and control systems)	154
Figure 10.1: Terneuzen locks.....	155
Figure 10.2: Artist impression of the new lock	156
Figure 10.3: Western lock.....	156
Figure 10.4: Western lock design details	157
Figure 10.5: Western lock gate centering device.....	157
Figure 10.6: Western lock undercarriage centering device.....	158
Figure 10.7: Western lock leveling system	158
Figure 10.8: Western lock curved beam on movable bridge.....	159
Figure 10.9: Meppelerdiep lock - the weir with the two sets miter gates underneath the bridge.....	160
Figure 10.10: Diagram of the Meppelerdiep lock.....	160
Figure 10.11: Placement of the inner head gate in the recess by two hydraulic cranes	160
Figure 10.12: Machinery layout new Meppelerdiep lock.....	161
Figure 10.13: Meppelerdiep new machinery	161
Figure 10.14: Meppelerdiep new undercarriage	162
Figure 10.15: Meppelerdiep new undercarriage support system	162
Figure 10.16: Meppelerdiep new guide roller system	163
Figure 10.17: Rolling gate – Northern Lock	164
Figure 10.18: Vessel passing through Northern Lock (courtesy RWS).....	164
Figure 10.19: Removable rail assembly.....	165
Figure 11.1: Double-leaf trunnion bascule bridge – Intercoastal waterway, Florida, USA	167
Figure 11.2: Two trunnion bascule bridges and lock with five rolling gates, Westsluis Terneuzen, the Netherlands.....	167
Figure 11.3: Rolling bascule bridge over Welland Canal, Canada.....	168
Figure 11.4: Rolling bascule bridge, Miami, Florida, USA.....	168
Figure 11.5: Remote-counterweighted bascule bridge, Strauss heel-trunnion type, Antwerp, Belgium.....	169
Figure 11.6: Remote-counterweighted bascule bridge, Strauss heel-trunnion type, Chicago, Illinois, USA	169
Figure 11.7: Remote-counterweighted bascule bridge, the Netherlands	170
Figure 11.8: Remote-counterweighted bascule bridge	170
Figure 11.9: Non-counterweighted bascule bridge, Kampen, the Netherlands and St. Mary's lift bridge	171

Figure 11.10: Samuel Beckett swing bridge – Dublin Ireland	172
Figure 11.11: Connaught, an un-symmetrical swing bridge, London, United Kingdom	172
Figure 11.12: Vertical lift railroad bridge, Trollhattan, Sweden	173
Figure 11.13: Vertical lift bridge 2 in background, St. Lambert lock, Montreal Canada	173
Figure 11.14: Hood Canal Bridge, Washington State, USA. The USS Ohio submarine navigates through the open draw span.	174
Figure 11.15: Floating bridge, the Netherlands.....	174
Figure 11.16: Ramspol bridge (zero energy bridge)	183
Figure 11.17: Batteries, which can provide electrical energy for several days and are being charged by solar panels	184
Figure 11.18: Energy from downwards movement of the bridge deck is transferred into electrical energy which is being stored.	184
Figure 12.1: Bridge 3 – Upper vertical lift bridge – St. Lambert lock – St. Lawrence Seaway	186
Figure 12.2: St. Lambert lock with Bridge 2 in background.....	186
Figure 12.3: Drive machinery – Bridge 3 – St. Lambert lock – St. Lawrence Seaway	187
Figure 12.4: Aerial view of Botlek bridge	188
Figure 12.5: Drive and balance cable reeving diagram – Botlek bridge.....	188
Figure 12.6: Drive system for Botlek bridge.....	189
Figure 12.7: Brake system for Botlek bridge.....	189
Figure 12.8: Cable tension system for Botlek bridge	189
Figure 12.9: State of Florida, Ft Lauderdale Atlantic Avenue, hydraulic driven bascule bridge – 4 cylinders per span	190
Figure 12.10: Gear rack and drive system on 1991 bridge span – Brienenoord bridge.....	191
Figure 12.11: Curved rack system for 1965 bridge span	191
Figure 12.12: Drive system for 1965 bridge span	192
Figure 12.13: Scherzer type rolling lift bridge components	192
Figure 12.14: Rolling bascule bridge Côte Ste. Catherine Lock – St. Lawrence Seaway	193
Figure 12.15: Drive machinery for rolling bascule bridge Côte Ste. Catherine lock – St. Lawrence Seaway	193
Figure 12.16: Beauharnois lock, St. Lawrence Seaway, Bridge 8 (swing bridge) that spans across the lock	194
Figure 12.17: Beauharnois lock, St. Lawrence Seaway, drive rack gear	195
Figure 12.18: Bonneville swing bridge	195
Figure 12.19: Bonneville swing bridge hydraulic drive	196
Figure 12.20: Brake types.....	197
Figure 12.21: Brake – two stage and thruster type brake	197
Figure 12.22: Duluth USA vertical lift bridge with operating house on span	201
Figure 13.1: Traffic control – Atlantic Avenue bascule bridge – Florida USA.....	204
Figure 13.2: AIS vessel detector schematic and vessel detector.....	205
Figure 13.3: Lock and bridge operating screens – St. Lawrence Seaway	206
Figure 13.4: Vehicle presence detector	207
Figure 13.5: Distribution of passings during amber and red light phase	211
Figure 13.6: Vehicle energy absorber (arresting device)	212
Figure 13.7: Vehicle arresting device	212
Figure 13.8: Vehicle barrier and arresting device	213
Figure 13.9: Vertical drop barrier – St. Lawrence Seaway.....	213
Figure 14.1: Ketelbrug Netherlands.....	214
Figure 14.2: Curved rack gear of Ketelbrug.....	215
Figure 14.3: Drive machinery for Ketelbrug	215
Figure 14.4: Panama wheel drive for Ketelbrug.....	216
Figure 14.5: Ketelbrug Panama drive machinery.....	216
Figure 14.6: Balancing Panama wheel and wheel end stop	217
Figure 14.7: Machinery buffer system	217
Figure 14.8: Centrifugal brakes	218
Figure 14.9: Overview of project area – Botlek bridge	220
Figure 14.10: Old and new bridges besides each other	220
Figure 14.11: Existing Botlek bridge	221
Figure 14.12: General design with indication of major components	221
Figure 14.13: Overview of driveline	223
Figure 14.14: Cable drum.....	223
Figure 14.15: Gear box, motors and brake	224
Figure 14.16: Arpex coupling.....	224
Figure 14.17: Gearbox (open)	225
Figure 14.18: Gearbox installed.....	225
Figure 14.19: Bridge locking system.....	225
Figure 14.20: Control centre in Rhoon.....	226

Figure 14.21: Manufacturing of steel bridge deck on yard in Schiedam	227
Figure 14.22: Third bascule bridge was erected on site in 1989.....	228
Figure 14.23: Bridge drive machinery 1965 bridge span	229
Figure 14.24: Pinion drive 1965 bridge.....	229
Figure 14.25: Curved rack and spiral construction seen when the bridge is in open position.....	230
Figure 14.26: New 1991 bridge rack drive.....	230
Figure 14.27: 1991 bridge in open position, seen from main pivoting point.....	231
Figure 14.28: Bridge locking device schematic.....	232
Figure 14.29: Bridge locking device elevation view and locking strut	232
Figure 14.30: Locking strut	233
Figure 14.31: Locking system overall view	233
Figure 15.1: View of the new and the old Kattwyk bridge	235
Figure 15.2: Access to the new and old Kattwyk bridge	235
Figure 15.3: Drive system of the Kattwyk lifting bridge	236
Figure 15.4: Rope drum and gear box of the Kattwyk bridge.....	236
Figure 15.5: Arrangement of the old Rethe bridge and the two new Rethe bridges (one closed one opened) © Hamburg Port Authority	237
Figure 15.6: Interlocking of the arms © Hamburg Port Authority	238
Figure 15.7: Drive cylinder © Hamburg Port Authority.....	238
Figure 15.8: Swing bridge at the North Lock.....	239
Figure 15.9: Swing bridge at the North Lock in opened position.....	239
Figure 16.1: Bridge #5 looking North from the approach wall at Lock 4	242
Figure 16.2: Bridge #5 schematic – Welland Canal.....	243
Figure 16.3: Bridge #5 counterweight and counterweight balance chains	243
Figure 16.4: Bridge #5 drive machinery	244
Figure 16.5: Bridge #5 central drive machinery	244
Figure 16.6: Bridge #5 lock actuator.....	245
Figure 16.7: Bridge #5 control instrumentation.....	245
Figure 16.8: Main sheave automatic lubricant box	247
Figure 16.9: Lubrication preventative maintenance programme – cleaning and re-lubricating.....	248
Figure 16.10: Maintenance stairs	248
Figure 16.11: Festoon cables before redesign	249
Figure 16.12: Festoon mechanical arm	249
Figure 16.13: Bridge 6, E&W looking south towards Locks 4, 5 & 6.....	250
Figure 16.14: Bridge 6, E&W looking west	250
Figure 16.15: Bridge 6, E&W looking east.....	251
Figure 16.16: Central drive machinery.....	252
Figure 16.17: Rolling elements of bridge	252
Figure 16.18: Swinging electrical leads	253
Figure 16.19: E-stops and bridge lock release	255
Figure 16.20: Operators station	255
Figure 17.1: Tower Bridge	256
Figure 17.2: Tower Bridge with bascule section open	257
Figure 17.3: Internal Bascule Chamber	257
Figure 17.4: Tower Bridge engine room © Tower Bridge Exhibition, City of London Corporation	258
Figure 17.5: Old control room.....	258
Figure 17.6: The original hydraulic and mechanical operating equipment.....	259
Figure 17.7: New accumulator.....	260
Figure 17.8: Glass Walkway©Barksy Media.....	260
Figure 17.9: Poole bridge looking from South.....	261
Figure 17.10: Drive machinery diagram.....	262
Figure 17.11: Poole bridge in opened position	263
Figure 17.12: Poole bridge in closed position	263
Figure 17.13: Twin Sails bridge at night	264
Figure 17.14: Twin Sails bridge showing hydraulic cylinder connections	265
Figure 17.15: Bridge in raised position	265
Figure 17.16: Hydraulic cylinder installation	266
Figure 18.1: Overall view of Duluth lift bridge in raised position	267
Figure 18.2: Bridge partially raised – note the pilot house in middle.....	268
Figure 18.3: View of original bridge in 1905.....	269
Figure 18.4: Counterweight and counterweight cables.....	270
Figure 18.5: Control panel includes both a master and slave panel	270
Figure 18.6: Winch drum for lifting cables.....	271
Figure 18.7: New AC Motor and brake from 2001	271
Figure 18.8: Entrance to bridge and harbour looking out towards Lake Superior.....	271
Figure 18.9: Duluth lift bridge during December 2013 storm	273

Figure 18.10: Control board and video displays from cameras.....	273
Figure 18.11: Skew indicator for bridge	274
Figure 18.12: Rock Island swing bridge in open position and barge going through Lock 15	275
Figure 18.13: Rock Island Swing Bridge – Lock 15 – United States.....	276
Figure 18.14: Rock Island Swing Bridge in turning position.....	277
Figure 18.15: Bridge drive – chain and turn table drive system and pony wheels	278
Figure 18.16: Bridge drive another view showing chain and pony wheels.....	278
Figure 18.17: Bridge centre drive, turn table and connecting rods	279
Figure 18.18: Rail deck and rail lock cylinders.....	279
Figure 18.19: Temporary power unit.....	280
Figure 18.20: End lift cylinder failure	280
Figure 18.21: Drive gear sets	280
Figure 18.22: Bevel drive gear set.....	281
Figure 18.23: Bridge power system	281
Figure 18.24: Movable bascule bridge – Ft Lauderdale, Florida.....	283
Figure 18.25: 5 th Street Bridge, Miami, Florida, USA.....	285
Figure 18.26: Cortez Bridge, connecting Bradenton and Anna Marie Island, Florida, USA (Gulf side)	286
Figure 18.27: Bonneville swing bridge.....	287
Figure 18.28: Bridge center support pier	288
Figure 18.29: Bridge opening	288
Figure 18.30: Centre bearing.....	289
Figure 18.31: Centre bearing with individual pucks concave down	289
Figure 18.32: Balance wheels	290
Figure 18.33: Balance wheel detail.....	290
Figure 18.34: Drive cylinders	291
Figure 18.35: Hydraulic power system including reservoir and drive motors.....	292