

INTERNATIONAL NAVIGATION
ASSOCIATION



ASSOCIATION INTERNATIONALE
DE NAVIGATION

Environmental Guidelines for Aquatic, Nearshore and Upland Confined Disposal Facilities for Contaminated Dredged Material



INTERNATIONAL NAVIGATION ASSOCIATION

- 1 Introduction**
 - 1.1 Description of the Task
 - 1.2 Purpose and Scope of the Report
 - 1.3 Types of CDFs
 - 1.3.1 Upland CDF
 - 1.3.2 Island/Nearshore CDF
 - 1.3.3 Subaquatic CDF
- 2 Framework for Planning, Design, and Implementation of a CDF**
 - 2.1 Introduction
 - 2.2 The CDF Technical Framework (CDFTF)
 - 2.3 CDF Planning (Phase A)
 - 2.3.1 Definition of CDF Requirements and Information
 - 2.3.2 Regulatory Requirements
 - 2.3.3 Identification and Selection of Potential CDF Sites
 - 2.4 CDF Design (Phase B)
 - 2.4.1 Conceptual Design(s)

2.4.2	Feasibility of Design and Selection of Final CDF Site
2.4.3	Detailed Design
2.5	CDF Implementation (Phase C)
2.5.1	Construction
2.5.2	Operation
2.5.3	Monitoring
2.5.4	Long-term Management
2.6	Public Consultation
3	Regulations and legislation
3.1	Introduction
3.2	Survey of international environmental regulations
3.3	Contaminated dredged material disposal policies
4	Site and Sediment characterization
4.1	Data needed
4.2	Properties of the material to be deposited in the CDF
4.2.1	Sampling
4.2.2	Physical characterization
4.2.3	Chemical characterization
4.3	Site characterization
4.3.1	Geotechnical data
4.3.2	Groundwater and surface water hydraulics
4.3.3	Meteorological data
4.3.4	Land use and Environmental Setting
5	Processes and Potential Environmental Impact
5.1	Introduction
5.2	Internal Processes
5.2.1	Sediment processes
5.2.2	Water balance in CDF
5.2.3	Chemical processes (oxidation, reduction and diffusion)
5.2.4	Biological processes in CDFs
5.2.5	Pre-treatment and treatment processes
5.3	Potential impacts
5.3.1	Groundwater flow
5.3.2	Surface Water Flow and Sediment Transport
5.3.3	Water quality
5.3.4	Potential impacts on ecology
5.3.5	Air quality
5.3.6	Noise levels
5.3.7	Visual considerations
5.3.8	Traffic
5.4	Contaminant Pathway Tests for Upland and Nearshore CDFs
5.4.1	Effluent during Filling
5.4.2	Surface Runoff
5.4.3	Leachate
5.4.4	Plant and Animal Uptake
5.4.5	Volatilization
6	Design and Construction
6.1	Introduction
6.2	Design Approach
6.3	Volume Requirements
6.4	Geometry and Dimensions
6.5	Containment Dikes and Structures
6.5.1	Retaining Dikes for Upland and Island/Nearshore
6.5.2	Aspects of dike design in open water
6.5.3	Outlet Weir Structures
6.6	Isolating Features and Contaminant Pathway Controls
6.6.1	Pathway Evaluations
6.6.2	Contaminant Controls
6.6.3	Use of Long Term Isolation Features
6.6.4	Isolation by Selective Placement
6.6.5	Engineered Controls
6.6.6	Discharge Control
6.7	Subaquatic Cap Design
6.8	Long-term Consolidation and Dewatering
6.9	Construction Considerations
6.10	Detailed Design Guidance
7	Management and Operational Aspects
7.1	General
7.2	Methods of Placement for Upland and Nearshore CDFs

7.2.1	Direct Pumping
7.2.2	Hydraulic Offloading
7.2.3	Mechanical Rehandling from Barges
7.2.4	Direct Placement by Barge
7.2.5	Truck or Railway Transportation
7.3	Placement Methods for Subaqueous CDFs
7.3.1	Introduction
7.3.2	Placement in Subaqueous CDFs
7.3.3	Cap Placement
7.3.4	Water Level Management
7.3.5	Scheduling and Sequencing of Operations
7.3.6	Long-term Management for Dewatering
7.4	Safety and Health
7.4.1	Introduction
7.4.2	Compliance with Law
7.4.3	Safety and Health Plan
7.4.4	Protection of the Workers
7.4.5	Protection of the Public
8	Monitoring
8.1	General Aspects
8.2	Monitoring plan
8.3	Baseline Monitoring
8.4	Monitoring During Operations
8.4.1	Subaquatic CDFs
8.4.2	Upland and Nearshore CDFs
8.4.3	Materials in the CDF
8.5	Monitoring after Completion
8.6	Management Actions
8.7	Reports
9	Long-term Management and Subsequent site use
9.1	Legal Aspects and Ownership
9.2	Inspection and Maintenance
9.3	Disaster Management
9.4	Subsequent Site Use
10	Conclusions and Recommendations
10.1	Introduction
10.2	General Conclusions and Recommendations
10.3	Specific Conclusions and Recommendations
10.3.1	Legislation and regulations
10.3.2	Site and Sediment Characterization
10.3.3	Processes and potential environmental impacts
10.3.4	Design and Construction
10.3.5	Operation
10.3.6	Monitoring
10.3.7	Long-term Management
11	Reference
	Annex I
	CD-ROM