



PIANC

The World Association for Waterborne
Transport Infrastructure

RECOMMENDATIONS FOR THE DESIGN AND ASSESSMENT OF SINGLE POINT (SPM) AND MULTI POINT MOORING (MPM) FACILITIES



MarCom Working Group Report N° 200 – 2023

PIANC REPORT N° 200
MARITIME NAVIGATION COMMISSION

**RECOMMENDATIONS FOR THE DESIGN
AND ASSESSMENT OF SINGLE POINT (SPM)
AND MULTI POINT MOORING (MPM) FACILITIES**

March 2023

PIANC has Technical Commissions concerned with inland waterways and ports (InCom), coastal and ocean waterways (including ports and harbours) (MarCom), environmental aspects (EnviCom) and sport and pleasure navigation (RecCom).

This report has been produced by an international Working Group convened by the Maritime Navigation Commission (MarCom). Members of the Working Group represent several countries and are acknowledged experts in their profession.

The objective of this report is to provide information and recommendations on good practice. Conformity is not obligatory and engineering judgement should be used in its application, especially in special circumstances. This report should be seen as an expert guidance and state-of-the-art on this particular subject. PIANC disclaims all responsibility in the event that this report should be presented as an official standard.

PIANC HQ
Boulevard du Roi Albert II 20 B. 3
1000 Brussels | Belgium

<http://www.pianc.org>

VAT BE 408-287-945

ISBN 978-2-87223-023-5

© All rights reserved

TABLE OF CONTENTS

1	INTRODUCTION	8
1.1	Background	8
1.2	Scope of the Guideline	8
1.2.1	Purpose and Objectives	9
1.2.2	Applicability	9
1.2.3	Overview	9
1.3	Definitions and Abbreviations	10
1.4	Working Group	12
1.4.1	Members of the Working Group	12
1.4.2	Meetings of the Working Group	14
1.5	Acknowledgments	14
2	Concepts: Type of SPM or MPM Facilities	15
2.1	Single Point Mooring Systems	16
2.1.1	CALM (Catenary Anchor Leg Mooring)	16
2.1.2	SALM (Single Anchor Leg Mooring)	17
2.1.3	Fixed Towers	18
2.2	Multi Point Mooring Systems	19
3	Considerations for Concept Selection	21
3.1	Selection of Systems	21
3.2	Metocean Aspects	22
3.2.1	General Conditions	22
3.2.2	Site-Specific Conditions	23
3.3	Design Conditions and Operational Limits	24
3.4	Environmental Impact	25
3.5	Bathymetry, Geotechnical and Geophysical Aspects	25
3.6	Target Fleet	26
3.7	Navigational Aspects	27
3.8	Other Site Constraints and Opportunities	28
3.9	Cost Implications	28
3.9.1	Cost Estimate and Accuracy Ranges	28
3.9.2	Main Costs	29
3.9.3	Cost Comparison for SPM and MPM	30
4	Functional Requirements, Planning and Basis of Design	31
4.1	Functional Requirements	32
4.2	Terminal Planning	33
4.2.1	Site Investigations	34
4.2.2	Site Selection	34
4.3	Site Conditions	34
4.4	Basis of Design	36
5	Single Point Mooring Systems	37
5.1	Catenary Anchor Leg Mooring (CALM)	37
5.1.1	Background	37
5.1.2	Navigational Considerations & Typical Layouts	39
5.1.3	Buoy Components	41
5.1.4	Anchor Legs & Foundation	44
5.1.5	Hawsers and Tanker Fittings	46
5.1.6	Floating Hoses	47
5.1.7	Risers	48
5.1.8	PLEMs	50
5.1.9	Telemetry	50
5.1.10	Design Considerations	51
5.1.11	Operational Considerations	52
5.1.12	Advantages and Disadvantages	53
5.2	Single Anchor Leg Mooring (SALM)	54
5.2.1	Background	54

5.2.2	Navigational Considerations and Typical Layouts.....	55
5.2.3	Buoy Components.....	55
5.2.4	Anchor Chain.....	56
5.2.5	Hose	58
5.2.6	PLEMs and Foundation.....	58
5.2.7	Aids to Navigation and Electrical	58
5.2.8	Design Considerations	59
5.2.9	Operational Considerations	60
5.2.10	Advantages and Disadvantages	60
5.3	Tower Systems.....	61
5.3.1	Background.....	61
5.3.2	Concepts.....	62
5.3.3	Navigational Considerations and Typical Layouts.....	63
5.3.4	Tower System Components	63
5.3.5	Design Considerations	66
5.3.6	Operational Considerations	66
5.3.7	Advantages and Disadvantages	68
6	Multi Point Mooring Systems	69
6.1	Multi Buoy Mooring Systems (MBM)	69
6.1.1	Background.....	69
6.1.2	Navigational Aspects.....	69
6.1.3	Orientation and Typical Layouts	70
6.1.4	Mooring Buoys.....	72
6.1.5	Mooring Legs and Foundation	73
6.1.6	Swamped Mooring.....	74
6.1.7	Preventer Wires/Ropes	75
6.1.8	Ancillary Equipment	75
6.1.9	Loading and Unloading Systems	76
6.1.10	Aids to Navigation	78
6.1.11	Design Considerations	78
6.1.12	Operational Considerations	78
6.2	Spread Mooring Systems (SMS)	80
6.2.1	Background.....	80
6.2.2	Tandem.....	81
6.2.3	Side-by-Side.....	85
6.3	Other Concepts of Multi Mooring Systems	89
7	Mooring Assessment	91
7.1	Vessel Mooring Equipment	92
7.2	Methodology	94
7.2.1	Codes/Standards	95
7.2.2	Required Data	95
7.3	Numerical Modelling.....	96
7.3.1	Frequency Domain/Time Domain Analysis	96
7.3.2	Quasi Static Analysis.....	97
7.3.3	Dynamic Analysis.....	97
7.4	Model Tests.....	98
7.4.1	ITTC International Towing Tank Conference	98
7.4.2	Physical Models.....	98
7.4.3	Model Basin Facility	98
7.5	Mooring Analysis Results	99
7.5.1	General.....	99
7.5.2	Vessel Motions.....	99
7.5.3	Mooring Line Tensions.....	101
7.5.4	Subsea Hoses	102
7.5.5	Capacity of Mooring Elements	102
8	Durability.....	103
8.1	Steel Corrosion.....	103
8.1.1	Chains	104

8.1.2	Corrosion Rates	104
8.1.3	Accelerated Low Water Corrosion (ALWC).....	105
8.2	Corrosion Protection	106
8.2.1	Allowing for Corrosion Rates.....	106
8.2.2	Coating Systems	107
8.2.3	Cathodic Protection	110
8.2.4	Alternative Materials	110
9	Risk Assessment	111
10	Operations and Safety	112
10.1	Operations	112
10.1.1	Operating Procedures	112
10.1.2	Staffing and Training.....	113
10.1.3	Berth/Vessel Capability Criteria	114
10.1.4	Pre-Arrival Information.....	114
10.1.5	Tug Requirements for Berthing and Unberthing	115
10.1.6	Manoeuvring.....	116
10.1.7	Mooring Plan	117
10.1.8	Vessel/Terminal Access	118
10.1.9	Communications	118
10.1.10	Pre-Cargo Transfer Conference and Inspection	118
10.1.11	Cargo Transfer Equipment and Operation.....	119
10.1.12	Inert Gas System	121
10.2	Requirements to Contain and Control Hazardous Situations	121
10.3	Emergency and Contingency Plan.....	121
10.3.1	Spill Response Plan	122
10.3.2	Spill Response Equipment	122
10.3.3	Spill Response Drills and Training	123
10.3.4	Emergency Shutdown Systems	123
10.3.5	Emergency Evacuation	124
10.4	Security Philosophy.....	124
10.5	Exclusion Zones	125
11	Guidelines and Recommendations for the Tendering Processes	127P
12	Fabrication, Installation & Commissioning	129
12.1	Single Point Mooring System (SPM)	129
12.1.1	Applicable Codes and Standards	129
12.1.2	Fabrication	130
12.1.3	Preparations	130
12.1.4	Installation	130
12.1.5	Testing and Commissioning	136
12.1.6	Installation and Commissioning of Tower/Turrets	137
12.2	Multi Point Mooring System (MPM)	138
12.2.1	Applicable Codes and Standards	138
12.2.2	Fabrication	138
12.2.3	Preparations	139
12.2.4	Installation	139
12.2.5	Testing and Commissioning	141
13	Certification & Classification.....	142
13.1	Single Point Mooring System (SPM)	143
13.2	Multi Point Mooring System (MPM)	144
13.2.1	Multiple Buoy Mooring Systems	144
13.2.2	Chain	144
13.2.3	Anchors.....	144
14	Inspection & Maintenance	145
14.1	Reference Documents for Inspection and Maintenance of SPM and MPM Terminals	145
14.2	Inspection and Maintenance Philosophy.....	145
14.3	Inspection and Maintenance Strategies	145
14.4	Recommendations and Considerations for Inspection and Maintenance	146
14.4.1	Dredging.....	147

15	Approach to Repair/Retrofit	148
15.1	Introduction	148
15.2	Existing Condition Assessment.....	149
15.3	Concept of New Use/Condition of Use	150
15.4	Guidelines for Approach to Retrofit/Upgrade	150
16	Decommissioning of SPM and MPM Terminals	151
16.1	Introduction	151
16.2	Existing Condition Assessment.....	153
16.3	Guidelines for Decommissioning.....	153
17	References	154
	Terms of Reference	157